

RISERPACK®

Ultimate Assembly Dimensions



AGF Ultimate RISERPACK

- Schedule 10 (Optional Schedule 40)
- Rolled Grooves (Cut Groove on Schedule 40)
- Butterfly Valve, Check Valve, or Both
- Flexible Stainless Steel Drain Line
- Includes Pressure Relief Valve with Drain Trim
- Horizontal or Vertical Installation
- Optional Domestic Components
(dimensions for domestic assemblies will differ from below)

AGF Corner Mount Ultimate RISERPACK

- Schedule 10 (Optional Schedule 40)
- Rolled Grooves (Cut Groove on Schedule 40)
- Butterfly Valve, Check Valve, or Both
- Flexible Stainless Steel Drain Line
- Includes Pressure Relief Valve with Drain Trim
- Horizontal or Vertical Installation
- Optional Domestic Components
(dimensions for domestic assemblies will differ from below)

| Size | 8011 URP | 8011 CV | 8011 BV |
|------|----------|---------|---------|
| | LENGTH | | |
| 2" | 24" | 20.75" | 17.25" |
| 2.5" | 25" | 21.25" | 17.75" |
| 3" | 25.5" | 21.75" | 17.75" |
| 4" | 26.625" | 22.125" | 18.5" |
| 6" | 30.75" | 25.5" | 19.25" |
| 8" | 33.875" | 28" | 19.875" |
| Size | WEIGHT | | |
| 2" | 42 lbs | 25 lbs | 34 lbs |
| 2.5" | 46 lbs | 28 lbs | 36 lbs |
| 3" | 53 lbs | 35 lbs | 40 lbs |
| 4" | 74 lbs | 52 lbs | 54 lbs |
| 6" | 113 lbs | 81 lbs | 71 lbs |
| 8" | 181 lbs | 111 lbs | 110 lbs |

| Size | 8611 URP | 8611 CV | 8611 BV |
|------|----------|---------|---------|
| | LENGTH | | |
| 2" | 24" | 20.75" | 17.25" |
| 2.5" | 25" | 21.25" | 17.75" |
| 3" | 25.5" | 21.75" | 17.75" |
| 4" | 26.75" | 22.125" | 18.625" |
| 6" | 30.625" | 26.75" | 19.825" |
| 8" | 33.625" | 28.375" | 19.25" |
| Size | WEIGHT | | |
| 2" | 42 lbs | 25 lbs | 34 lbs |
| 2.5" | 46 lbs | 28 lbs | 36 lbs |
| 3" | 53 lbs | 35 lbs | 40 lbs |
| 4" | 74 lbs | 52 lbs | 54 lbs |
| 6" | 113 lbs | 81 lbs | 71 lbs |
| 8" | 181 lbs | 111 lbs | 110 lbs |



AGF Manufacturing Inc.
100 Quaker Lane, Malvern, PA 19355

610-240-4900
techsupport@agfmfg.com

www.agfmfg.com